Complete Streets Funding Program

Project Prioritization Plan

Municipality	Westport
MassDOT District	5
Name	Amy Messier
Title	Assistant Town Planner
Date	8/25/2022

Public Engagement
Public Engagement Description
The Town of Westport and SRPEDD hosted an existing conditions public workshop via Zoom to gather feedback from the town on projects they wanted to see added to this list. We also hosted a second workshop to discuss the final projects that were added to the Prioritization Plan.

Project Basics				Location		Modes Served				Project Types																								Assessment									Funding Request			Construction Schedule
										Intersection Redesign			Street Reconfigurations & Traffic Calming			Pedestrian Crossing Modifications					Pedestrian & Bike Network Connections			Transit Investments			Environment & Streetscape Investments					Network Gap	High Crash Location											
Project Priority Ranking	Project Name	Project Description	Project Source	Project Location	Google Map Link	Pedestrian	Bicycle	Transit	Vehicle/Freight	Intersection Realignment	Signalization	Roundabout/Rotary Installation	Road Diet/Lane Reduction	Road Widening	Traffic Calming Measures	Crosswalk Improvements	Pedestrian Bridge	Pedestrian Tunnel	Pedestrian Overpass	Crosswalk Signal	Crosswalk Beacon	Sidewalk	Shared Use Path/Trail	Bicycle Lane	Bicycle Parking	Bicycle Signal	Transit Service Improvements	Transit Signal Priority	Street Lighting	Wayfinding Signage	Bicycle Parking	Bicycle Signage	Other Streetscape Improvements	Is a Network Gap being filled?	Pedestrian	Bicycle	Vehicle	Environmental Justice	Safe Routes to School	Safe Routes to Seniors	Accessibility	State-owned ROW	Estimated Project Cost Range	Funding Requested from MassDOT	Other Funding Source(s) & Amount (if applicable)	Anticipated Construction Duration
																																						Is an Environmental Justice Population Served? (See MassGIS Map)	Does this project improve safety or accessibility within one mile of a school?	Does this project improve safety or accessibility within 1/4 mile of a Senior destination?	Does this project improve conditions for people with disabilities?	Does this project include any state-owned right-of-way?				
1	Sanford Road Shared Use Path	Narrow existing travel lanes and construct a 10-foot wide shared use path separated from traffic with 5-foot wide or greater buffer along one side of the road. Construct a 6-foot sidewalk on the opposite side.	CS Needs Assessment	American Legion Highway (Route 177) to State Road (Route 6)	https://goo.gl/maps/uvG4AVzxbCKB2dQ6	Yes	Yes	No	No	No	No	No	No	No	No	Yes	No	No	No	No	Yes	Yes	Yes	No	No	No	No	No	Yes	No	No	No	No	Yes	No	No	No	Yes	No	No	Yes	No	>$400,000	$400,000	TIP	12
2	State Road (Route 6) Bicycle and Pedestrian Improvements	Reconfigure the existing roadway layout to add separated and safe facilities for bicyclists and pedestrians.	Other	Gifford Street to S Berryman Street	https://goo.gl/maps/APV9br3FAgBQaSA59	Yes	Yes	No	Yes	No	No	No	No	No	No	Yes	No	No	No	No	Yes	No	Yes	No	No	Yes	No	Yes	No	No	No	No	No	No	No	No	Yes	Yes	No	No	Yes	Yes	>$400,000	$ -	TIP	36
3	American Legion Highway (Route 177) Bicycle and Pedestrian Improvements	Reconfigure the existing roadway layout to add facilities for bicyclists and pedestrians.	CS Needs Assessment	Fall River Town Line to State Road (Route 6)	https://goo.gl/maps/hKvx3tmJzTBwuPQ6A	Yes	Yes	No	No	No	No	No	Yes	No	No	Yes	No	No	No	No	Yes	Yes	No	Yes	No	No	No	No	Yes	No	No	No	No	Yes	No	No	No	Yes	No	No	Yes	Yes	>$400,000	$ -	TIP	36
4	Westport Bike Path	Construct a 12-foot wide shared use path along an abandoned right of way from the Fall River City Line to Route 6.	Safety/Pedestrian/Bicycle Audit	From Fall River City Line to Route 6	https://goo.gl/maps/z2JRb7zxdSHXVJw6	Yes	Yes	No	No	No	No	No	No	No	No	Yes	No	No	No	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	Yes	No	No	No	No	No	No	Yes	No	$100,000 - $250,000	$208,120	-	12
5	Main Road Bicycle and Pedestrian Improvements (Section 1)	Install a new 5 foot wide asphalt sidewalk with granite curbing on the right side (east side) of the road. Add ADA/AAB compliant curb ramps with tactile warning panels and high visibility crosswalks at all pedestrian crossing locations (where necessary). Install sharrows and "Share the Road" wayfinding signage along both sides of the road.	Master Plan	Hix Bridge Road to Brookwood Drive	https://goo.gl/maps/qdWWdXvTvQkr5R9	Yes	Yes	No	No	No	No	No	No	No	No	Yes	No	No	No	No	Yes	Yes	Yes	No	No	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	No	No	Yes	No	>$400,000	$400,000	TIP, Chapter 90	6
6	Main Road Bicycle and Pedestrian Improvements (Section 2)	Install a new 5 foot wide asphalt sidewalk with granite curbing on the right side (east side) of the road. Add ADA/AAB compliant curb ramps with tactile warning panels and high visibility crosswalks at all pedestrian crossing locations (where necessary). Install sharrows and "Share the Road" wayfinding signage along both sides of the road.	CS Needs Assessment	Drift Road to Hix Bridge Road	https://goo.gl/maps/2BFBFBbpyGCCvb66	Yes	Yes	No	No	No	No	No	No	No	No	Yes	No	No	No	No	Yes	Yes	Yes	No	No	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	No	No	Yes	No	>$400,000	$400,000	Chapter 90	8
7	Old Bedford Road Bicycle and Pedestrian Improvements (Section 1)	Narrow existing travel lanes and construct a 8-10 foot wide shared use path separated from traffic along the left (north) side of the road. Add a 2' landscaped buffer between the roadway and the shared use path.	Safety/Pedestrian/Bicycle Audit	Sanford to Blossom	https://goo.gl/maps/mvWSMJvGKCuHmG7	Yes	Yes	No	No	No	No	No	Yes	No	No	Yes	No	No	No	No	Yes	No	Yes	No	No	No	No	No	Yes	No	No	No	No	Yes	No	No	No	Yes	No	No	Yes	No	$250,000 - $400,000	$127,090	-	9
8	Old County Road Pedestrian Improvements	Install a new 5 foot wide asphalt sidewalk with granite curbing on the left side (north side) of the road (Route 88 to approximately 400 Old County Road). Add ADA/AAB compliant curb ramps with tactile warning panels and high visibility crosswalks at all intersecting streets to enhance connection to the Westport Middle and High Schools as well as the Public Library.	CS Needs Assessment	Route 88 to Approximately 400 Old County Road	https://goo.gl/maps/KvQtqcrxBBr3qRbk17	Yes	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	Yes	Yes	Yes	No	No	No	No	No	No	No	No	No	No	No	Yes	No	No	No	Yes	Yes	Yes	Yes	No	>$400,000	$400,000	Chapter 90	5
9	Old Bedford Road Bicycle and Pedestrian Improvements (Section 2)	Narrow existing travel lanes and construct a 8-10 foot wide shared use path separated from traffic along the left (north) side of the road. Add a 2' landscaped buffer between the roadway and the shared use path.	Safety/Pedestrian/Bicycle Audit	Blossom to Town Line	https://goo.gl/maps/6BDeJ1Hhchq4KE4R9	Yes	Yes	No	No	No	No	No	Yes	No	No	Yes	No	No	No	No	Yes	Yes	Yes	No	No	No	No	No	Yes	No	No	No	No	Yes	No	No	No	Yes	No	No	Yes	No	>$400,000	$400,000	Chapter 90	9
10	Hix Bridge Road Bicycle and Pedestrian Improvements	Install a new 5 foot wide asphalt sidewalk with granite curbing on the right side (south side) of the road. Add ADA/AAB compliant curb ramps with tactile warning panels and high visibility crosswalks at all intersecting streets. Install sharrows and "Share the Road" wayfinding signage along both sides of the road.	CS Needs Assessment	Main Road to Route 88	https://goo.gl/maps/5wsw1Fzxe2K8Tn6t8	Yes	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	Yes	Yes	Yes	No	No	No	No	No	Yes	No	No	No	No	Yes	No	No	No	No	No	No	Yes	No	$250,000 - $400,000	$364,330	-	4
11	Old County Road Bicycle Improvements	Resurface and restripe roadway to provide 5 foot wide bicycle lanes with MUTCD approved bicycle lane pavement markings and bicycle lane signage (R5-17) on both sides of the road from Route 88 to the Dartmouth Town Line.	CS Needs Assessment	From Route 88 to Dartmouth Town Line	https://goo.gl/maps/ARdDCZRXFHTPAqA6	No	Yes	No	No	No	No	No	No	Yes	No	No	No	No	No	No	No	No	Yes	No	No	No	No	No	Yes	No	No	No	No	Yes	No	No	No	No	No	No	No	No	>$400,000	$400,000	TIP, Chapter 90	5
12	Gifford Road Pedestrian Improvements Section 1	Install a new 5 foot wide asphalt sidewalk with granite curbing on the left side (west side) of the road. Add ADA/AAB compliant curb ramps with tactile warning panels and high visibility crosswalks at all intersecting streets (where necessary) to enhance connection to the Macomber School and Route 6.	CS Needs Assessment	Kyle Jacob Road to State Road (Route 6)	https://goo.gl/maps/qCu1tQKv2BtoeBaa6	Yes	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	Yes	Yes	Yes	No	No	No	No	No	Yes	No	No	No	No	Yes	No	No	No	No	Yes	No	No	Yes	No	>$400,000	$400,000	Chapter 90	12
13	Gifford Road Pedestrian Improvements Section 2	Install a new 5 foot wide asphalt sidewalk with granite curbing on the left side (west side) of the road. Add ADA/AAB compliant curb ramps with tactile warning panels and high visibility crosswalks at all intersecting streets to enhance connection to the Macomber School and Route 6.	CS Needs Assessment	American Legion Highway (Route 177) to Kyle Jacob Road	https://goo.gl/maps/kcE1cbJCdnuvJCbb8	Yes	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	Yes	Yes	Yes	No	No	No	No	No	Yes	No	No	No	No	Yes	No	No	No	No	Yes	No	No	Yes	No	>$400,000	$400,000	Chapter 90	12
14	Main Road and Adamsville Rd Intersection Improvements	Narrow approaches to intersection and add bicyclist and pedestrian accommodations as needed. Add ADA/AAB compliant curb ramps with tactile warning panels and high visibility crosswalks.	CS Needs Assessment	Main Road and Adamsville Road	https://goo.gl/maps/33qq5Y5KJ8KpdZWp9	Yes	Yes	No	Yes	Yes	Yes	No	No	Yes	No	Yes	No	No	No	No	No	Yes	Yes	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	Yes	No	>$400,000	$400,000	TIP	4
15	Village Way Crosswalk and Rectangular Rapid Flashing Beacon (RRFB)	Install Rectangular Rapid Flashing Beacon (RRFB) at the Village Way crosswalk Main Road.	CS Needs Assessment	Village Way at Main Street	https://goo.gl/maps/MxJ4BwaLvVwCbE18	Yes	Yes	No	No	No	No	No	No	No	No	Yes	No	Yes	No	No	Yes	Yes	No	No	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	No	No	Yes	No	$50,000 - $100,000	$66,360	-	2
16	Bike Loop Sharrows/ Wayfinding	Install sharrows and "Share the Road" wayfinding signage along both sides of the road along Hixbridge Road, Horseneck Road, and East Beach Road to create a bike loop around the south end of Westport.	CS Needs Assessment	Hix Bridge Road, Horseneck Road, East Beach Road	https://goo.gl/maps/XKvEbKKJ2xZPbbq8	No	Yes	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	No	Yes	No	No	No	No	No	No	No	No	No	No	No	No	No	$100,000 - $250,000	$134,900	-	2
17	Bicycle Parking	Addition of bicycle parking at several locations including Town Hall, Town Hall Annex, Westport Public Schools, and Town Beaches	Master Plan	Town Facilities and Town Beaches	Town Hall, Town Hall Annex, Town Beach	No	Yes	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	No	No	No	No	No	No	No	<$50,000	$23,180	-	2
18	Blossom Road Bicycle and Pedestrian Improvements	Resurface the existing sidewalk on the left side of the road to provide a 5 foot wide walk surface. Add ADA/AAB compliant curb ramps with tactile warning panels and high visibility crosswalks at all pedestrian crossing locations (where necessary). Install sharrows and "Share the Road" wayfinding signage along both sides of the road.	CS Needs Assessment	Old Bedford Road to Fall River City Line	https://goo.gl/maps/wcnWXbAQJqZ2ag88	Yes	Yes	No	No	No	No	No	No	No	No	Yes	No	No	No	No	Yes	Yes	Yes	No	No	No	No	No	Yes	No	No	No	No	Yes	No	No	No	No	No	No	Yes	No	$250,000 - $400,000	$263,850	-	3
19	Main Road Pedestrian Improvements (Section 3)	Resurface the existing sidewalk on both sides of the road to provide a 5 foot wide walk surface. Add ADA/AAB compliant curb ramps with tactile warning panels and high visibility crosswalks at all pedestrian crossing locations (where necessary).	CS Needs Assessment	2056 Main Road to Drift Road	https://goo.gl/maps/HKz1BvbeRBdeJ32	Yes	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	Yes	Yes	Yes	No	No	No	No	No	No	No	No	No	No	No	Yes	No	No	No	No	No	No	Yes	No	>$400,000	$400,000	TIP, Chapter 90	5
20																																														
21																																														
22																																														
23																																														
24																																														
25																																														
26																																														
27																																														